



Oct. 2018 CJLR Site STA Bihong Ji 季必宏

Content 主要内容




- Background 背景
 - ✓ Case for Change 为何改变
- APQP Process Details APQP流程组成
 - ✓ APQP 49 Key Deliverables APQP的49个交付物
 - ✓ Priority Supplier Selection 关键供应商的选择
- APQP Reporting Meeting Process 汇报会议流程
 - ✓ APQP 4 Evaluation Meeting APQP 4次评审会议
 - ✓ APQP Readiness Assessment APQP状态评估表

CJLR STA Quality House CJLR STA 质量屋










Case for Change 为何改变





Case for Change 为何改变



New Product

Introduction

Processes not followed (training or

discipline)

CJLR and Supplier teamwork not robust enough

APQP not used robustly internally & externally

APQP Priority supplier identification & management is diluted

Lack of cross functional ownership

Not fully off tool at VP build Escalation of APQP outputs is absent from LMMs

Part problems found too late

Critical actions not progressed quickly enough

Suppliers not aware of APQP requirements early enough

> SEP Process not being followed or supported

> > Too much uncoordinated interaction between C JLR & Supplier

FIX: - Re-Launch Cross Functional APQP Team Engagement

PPAP L5 for all suppliers is

too resource

intense

Opportunity 机会



Early Involvement

早期参与



Work with suppliers more <u>consistently</u>, earlier in the product development process

在产品开发过程早期,与供应商更融洽地合作

Teams

团队



Utilize cross-functional teams to work together with suppliers at their facilities

利用跨功能团队与供应商一起在现场工作

Standardization

标准化



Adopt a single, global, disciplined process to minimize rework and redundancy

采用唯一的、全球通用的,有纪律的流程, 尽量减少返工和重复

Governance/Reporting

管理/汇报



Use common, clear deliverables and a structured management review cadence

使用共同的、明确的交付报告和结构化的管理评审模式

Principles of APQP Supplier Engagement 供应商参与APQP的主要原则



- Supplier launch success is a cross-functional, shared responsibility PMST- PD, STA, Buyers & MP&L are core team members
- 供应商投产的成功是跨职能部门共同的责任。核心团队成员包括PD, STA, 采购及物流。
- 2. PMST will work proactively with the highest leverage suppliers on a program 跨职能团队小组将在整个项目过程中与供应商一起工作
- 3. Supplier engagement will begin early in a program immediately after sourcing. 供应商将在项目早期,即选点后立即参与项目开发。
- 4. PMST will visit the key supplier manufacturing facility a minimum of four (4) times 跨职能团队将对关键供应商进行至少4次拜访。


Principles of APQP Supplier Engagement 供应商参与APQP的主要原则



- 5. PMST will provide the supplier with a single voice on key launch matters 在关键投产问题上,该团队将给供应商一致的声音。
- 6. Underlying APQP and PPAP processes and roles & responsibilities will remain the same 相关的APQP和PPAP流程及角色和职责将保持不变。
- 7. Team engagement will continue until the supplier has successfully completed all PPAP requirements and fully met all program ramp-up volumes 团队参与一直继续到供应商成功达到所有PPAP的要求,并能充分满足项目爬坡的要求。
- 8. CJLR will implement the supplier engagement process consistently on a global basis in alignment with the global makeup of the supply base 奇瑞捷豹路虎全球将实施一致的供应商参与流程。

APQP- Process Overview APQP的主要过程






Program Milestone Introduction 项目节点介绍



- PTCC-Program Target Compatibility Checkpoint
- PTC/M-1DJ- PTCC-Program Target Compatibility/M-1 Data Judgment
- PA-Program Approval
- FDJ-Final Data Judgment
- VP-1st Verification Prototype
- PEC-Preliminary Engineering Completion
- FEC-Final Engineering Completion
- LR-Launch Readiness
- TT-Tooling Trial-Build Start
- PP-Pilot Production-Build Start
- MP1-Mass Production 1-Build Start

Scope/Activity 范围/任务






Quality/Capacity Verification 质量/产能验证

Suppliers are integral to APQP with activity beginning at sourcing and continuing to MP2 -- all CJLR functional organizations are involved.

供应商是从开始选点到MP2等活动的重要环节---所有CJLR职能部门都参与其中

Process Flow 过程流程图





- Failure Mode Avoidance 失效模式避免
- Mfg./Capacity Planning 生产/产能计划
- Testing & ValidationPlanning测试与验证计划

- Testing & Validation 测试与验证
- Prototype Builds 样件制造
- Tooling 工装

- Testing & Validation 测试与验证
- Tooling Verification
 工装验证
- Manufacturing Launch 生产投产
- Quality / Capacity Verification 质量/产能验证

- Manufacturing Launch 制造投产
- Quality / Capacity Verification 质量/产能验证

APQP/PPAP Roles and Responsibilities APQP/PPAP的要素和职责

		Lead
1	Sourcing decision	Buyer
2	Customer input requirements	PD
3	Craftsmanship/appearance approval report	PD
4	DFMEA	PD
5	Design/manufacturing reviews	PD/STA
6	DVP&R material, performance test results	PD
7	Subcontractor APQP status	STA
8	Facilities, tools, & gauges	STA
9	Prototype build control plan	PD
10	Prototype builds	PD
11	Drawing & specification design records	PD
12	Engineering change document	PD
13	Team feasibility commitment/ customer engineering approval	PD/STA
14	Manufacturing process flowchart/ process flow diagram	STA





			主导	庐
	1	选点决定	采购	
	2	顾客要求输入	PD	
	3	精致工艺/外观批准报告	PD	
	4	设计失效模式及后果分析	PD	
	5	设计/制造评审	PD/STA	
	6	设计验证计划与汇报的材料和性能测试结果	PD	
_	7	分供方APQP状态	STA	
	8	设备、工具和量具	STA	
	9	样件制造计划	PD	
	10	样件制造	PD	
	11	图纸和规范设计记录	PD	
	12	工程变更文件	PD	
	13	小组可行性承诺/	PD/STA	
		顾客工程批准		
	14	制造过程流程图	STA	
	15	过程失效模式及后果分析	STA/PD	

APQP/PPAP Roles and Responsibilities APQP/PPAP的要素和职责



						一台场·健创路院
		Lead				主导
16	Measurement systems evaluation/	STA		16	测量系统评价/	STA
	Measurement System Analysis studies				测量系统分析研究	
17	Qualified laboratory documentation	STA		17	有资质的实验室证明文件	STA
18	Checking aids	STA		18	辅助检查工具	STA
19	Pre-launch control plan	STA		19	试生产控制计划	STA
20	Operator process instructions	STA	1	20	操作者作业指导书	STA
21	Packaging specifications	MP&L		21	包装规范	MP&L
22	Production trial run	STA		22	产品试生产	STA
23	Production control plan	STA		23	产品控制计划	STA
24	Dimensional results	STA		24	尺寸结果	STA
25	Initial process capability study	STA		25	初始过程能力分析	STA
26	Production validation testing	PD		26	生产确认试验	PD
27	Part submission warrant	STA/PD		27	产品提交保证书	STA/PD
28	Bulk material requirements	STA		28	辅料要求	STA
29	Sample product	STA		29	样件产品	STA



	APQP Element	Lead	Due*	Deliverables	
1.	Sourcing decision	Buyer	<ptcc></ptcc>	C> 1. Required Sourcing Agreement Signed	
			<pa></pa>	2. Required Supplier Commercial & Program Agreements Signed	
			<fdj></fdj>	3. All Production Tool Orders Issued to Suppliers	PDF
			<pa></pa>	4. Final Mix, Maximum Weekly Volume Communicated and Agreed	L551 PDS
2.	Customer input requirements	PD	<pa></pa>	5. Program Expectations Cascaded to Suppliers	
3.	Craftsmanship/ appearance approval report	PD	<tt></tt>	6. AAR Approved	W
			<pp></pp>	7. Color Changes Completed Supporting Color Harmony	AAR
4.	DFMEA	PD	<pa></pa>	8. DFMEA Completed	X
			<pa></pa>	9. Special Characteristics Cascaded to Suppliers	CCSC list
5.	Design/manufacturing reviews	PD/STA	<pp></pp>	10. Quality Issues Closed and Effective	
6.	DVP&R material, performance test results	PD	<tt></tt>	11. DV Testing Complete	
7.	Subcontractor APQP status	STA	<fdj></fdj>	12. Sub-supplier PPAP Timing Plan Completed	
			<tt></tt>	13. Sub-supplier PPAP Phase 1 (or equivalent) Completed	Sub-supplier
			<mp1></mp1>	14. Sub-supplier PPAP Phase 3 (or equivalent) Completed	APQP

Reporting will focus on measurable "Deliverables" that highlight APQP Element completion at a given program milestone



	APQP Element	Lead	Due*	Deliverables	
8.	Facilities, Tools & Gauges	STA	<fdj></fdj>	15. Facility and Tooling Timing Plan Completed	
			<tt></tt>	16. Facilities/Tools/Gauges are at the Final Production Location	PDF
			<ptc></ptc>	17. Supplier's OEE plan is Confirmed by Surrogate Data	t <mark>imi</mark> ng plan
			<pa></pa>	18. Gauge Plan (Including Released Gauge Drawings) Completed	
			<1⊺>	19. Supplier's Demonstrated OEE (Phase 0) supports capacity requirements	
9.	Prototype Control Plan	PD	<fdj></fdj>	20. Prototype Build Control Plan Completed	
10.	Prototype Build	PD	<fdj></fdj>	21. All Prototype Tool Orders Issued to Suppliers	X I
			<fdj></fdj>	22. Prototype Parts Ordered	
			<fdj></fdj>	23. Prototype Parts Achieve 100% of Required Print Specs.	
11.	Drawings & Specifications	PD	<psc></psc>	24. Design Styling Confirmation	X
			<fdj></fdj>	25. Design Release (WERS) Completed	tooling kick off letter
12.	Engineering Change	PD	<tt></tt>	26. All JLR Engineering Changes Approved & Recognized by the Supplier	support plan
13.	Team Feasibility	PD/STA	<fdj></fdj>	27. Design, Process, & Timing Feasibility Confirmation	
14.	Manufacturing Process Flow	STA	<pec></pec>	28. Final Process Flowchart Supports PPAP Phase 0 Event	Flow Chart




	•			المرادعي اللاراء		
	APQP Element	Lead	Due*	Deliverables		
15.	PFMEA	STA/PD	<vp></vp>	29. Final PFMEA Completed with Linkages	FMEA	
16.	Measurement System Analysis	STA	<it></it>	30. Gauge R&R Results <= 10% per PPAP Customer Specifics		
17.	Qualified Laboratory Documents	STA	<tt></tt>	31. Supplier Internal & External Laboratory Compliance		
18.	Checking Aids	STA	<tt></tt>	32. Checking Aids Compliant With Part Specifications		
19.	Pre-Launch Control Plan	STA	<pec></pec>	33. Pre-Launch Control Plan Completed with Linkages		
20.	Operator Instructions	STA	<pec></pec>	34. Operator Process Instructions Completed	EU1121	
21.	Packaging Specifications	MP&L	<tt></tt>	35. Packaging Approval Process Completed	× i	
22.	Production Trial Run	STA	<it></it>	36. PPAP Phase 0 (Including Sub-suppliers) Completed	@R checklist	
23.	Production Control Plan	STA	<it></it>	37. Production Control Plan Complete with Linkages	P	
24.	Initial Process Capability	STA	<tt></tt>	38. Initial Process Capability Results (Ppk >= 1.67)	R@R phase0	



	APQP Element	Lead	Due*	Deliverables	X III
25.	Dimensional Results	STA	<tt></tt>	30, 100% of Paguired Measured Points within Tolerance	PPIR
26.	PV Testing	PD	<tt></tt>	40. PV Testing Complete	PVR
27.	PSW	STA/PD	<tt></tt>		V1 cover
			<pec></pec>		sheet
			<pp></pp>	43. PPAP Phase 2 Completed	
			<mp1></mp1>	> 44. PPAP Phase 3 completed	
			<mp1></mp1>	45. Suppliers Demonstrated OEE Support Capacity Req.	
28.	Bulk Material Requirements	STA	<tt></tt>	46. Bulk Materials Checklist Included in PPAP Submission	
29.	Sample Product	STA	<tt></tt>	47. Sample Product Produced with CJLR Identification	
30.	Master Sample	STA	<tt></tt>	48. Master Sample Approved	
31.	Record of Compliance	STA	<tt></tt>	49. CJLR Specific Requirements Documented	

Priority Supplier Selection 优先级供应商选择






Priority Sites 优先级供应商



A program' s suppliers are defined as "Priority" and "Non-priority." Priority suppliers have new-tooled end items that present risks to the launch (site, part, or program risk).

项目的供应商分为"关键"和"非关键"供应商。"关键供应商有新开模具的零件且存在投产风险,如生产现场、零件和项目风险。



The APQP Supplier Engagement Process will focus cross-functional CJLR resources on the <u>Priority suppliers</u>.


APQP供应商参与流程将跨职能资源重点集中在关键供应商。

Priority Supplier Selection Process 优先级供应商选择流程



Priority Supplier Selection process is led by program STA and PD and reviewed by Site STA.

This process shall take place by the following:





PPAP requirements for Priority suppliers 优先级供应商的PPAP要求





-奇瑞·捷豹路虎-


供应商 JLRQ 状态 Supplier Site JLRQ Status 获得 JLRQ 认	新零件状态 New Part Status 非优先级	PPAP 提 交級别 PPAP Sub'n Level	<u>阶段 0</u> 节拍生产 <u>Phase 0</u> Run-At-Rate 供应商工厂根据P	<u>阶段 1</u> 质量验证 <u>Phase 1</u> Quality Verification	<u>阶段 2</u> 生产验证 <u>Phase 2</u> Production Verification	<u>阶段 3</u> 产能验证 <u>Phase 3</u> Capacity Verification
证 JLRQ	Non-Priority	1	Supplier site self-			
无论 JLRQ 认 证状态 Regardless of JLRQ status	不适用于新车型 Not Applicable for New Models	2	供应商将保证书、 STA Warrant with prod submitted to STA	luct samples and		
未获得 JLRQ 认证 Non JLRQ	非优先级 Non-Priority	3		工厂提交电子档 F view of Supplier S locumentation		ission and
无论 JLRQ 认 证状态 Regardless of JLRQ status	不适用于新车型 Not Applicable for New Models	4	供应商提交保证书和其它 STA 定义的提交要求 Warrant and other requirements as defined by STA			
无论 JLRQ 认 证状态 Regardless of JLRQ status	优先级 Priority	5	STA 参加 "节拍 生产"活动 STA attend Run at Rate event	STA 审核 PPAP 提交件,包括支 持数据和改进措 施报告 STA review PPAP submission, including supporting data and CAR.	如适用,STA 参加生产运 行,然后审核 PPAP 提交物 和改进措施报 告 If applicable, STA attend production run, then review PPAP submission and CAR. 如适用,PD	STA 参加生产 运行,并审核 PPAP 提交物 和改进措施报 告 STA attend production run, then review PPAP submission and CAR.


APQP Priority Supplier – 'The Critical Few Focus' APQP中优先级供应商的主要几个关注点



The APQP Priority Supplier process is a cross-functional process The process is governed by the following principles:


- Programme team will target the most critical suppliers based on risk 基于风险重点关注
- Cross functional ownership; PD, PUR, STA, Supplier 团队合作
- Supplier engagement early programme, immediately after sourcing 早期参与
- Cross functional teams will evaluate Supplier manufacturing facility a minimum of 4 times. 4次现场评审
- Team engagement continues until PPAP is complete PPAP完成后结束APQP





Team Formation 成立项目团队





Team Member Responsibilities 团队成员责任



While there is a team lead at all times, each team member still has the responsibility between meetings to: 虽然每项活动都有团队牵头人,但每个团队成员都有以下的共同责任:


- Resolve open concerns 解决未关闭的问题
- Communicate with other team members as needed 必要时与其他团队成员沟通
- Bring together other team members to close out concerns as necessary 适时让其他团队成员参与问题解决

It is recognized that all team members will interface with the supplier regularly between On-Site Evaluations, and in many cases, this interaction will occur at the supplier site.

所有团队成员在几次供应商现场拜访期间有互动沟通,且大多情况下都在供应商现场。

Team Kick-Off Meetings 项目团队启动会





Update of Verification Matrix – Supplier APQP/PPAP Readiness Assessment (Schedule A)

保密资料 CONFIDENTIAL

Team Kick-Off Meeting – Key Points 启动会议关键点



Purpose 目的:

Introduce CJLR and supplier team members

介绍奇瑞捷豹路虎及供应商的团队成员

- Provide them with an overview of the APQP Supplier Engagement Process
- APQP供应商参与流程概述
- Communicate team expectations prior to On-Site Evaluation #1. A key deliverable will be CJLR and supplier team
 agreement on the required program and process timing.
- 沟通第1次现场评审的期望。主要输出为奇瑞捷豹路虎及供应商就必要的项目和过程时间上达成一致。

Timing: PT: Unit <PTC> -- <PTCC>

UN: <PSC> - <PTCC>+90 Days

UP: <PTCC> - <PTC/M1DJ>

Note: Actual review timing will depend upon the specific needs of the component and program.

Team Kick-Off Meeting – Key Points 启动会议关键点



Participants:

Lead: PD Engineer

Support: STA Site Engineer, MP&L Representative (as required), Buyer

参加者:

牵头人: PD工程师


支持者: STA现场工程师、物流代表(若需要)、采购

Location:

CJLR facility, supplier facility, or teleconference (according to team preference). Meetings will typically last 2 – 3 hours. 地点: 奇瑞捷豹路虎工厂、供应商制造现场或电话会议(根据团队的愿望)。会议通常将持续2-3小时。

On-Site Evaluation #1 第一次现场评审会议





On-Site Evaluation #1 – Key Points 第一次现场评审会议关键点



Purpose目的:

Failure mode avoidance through detailed FMEA and Control Plan reviews

通过对FMEA及控制计划的评审确定失效模式并制定预防措施

■ Manufacturing Planning 生产规划

■ Capacity Planning 产能规划

Timing: PT: <PTCC> - <PTC/M1DJ>

UN: <PTCC> - <PTC/M1DJ>

UP: <PTC/M1DJ> - <PA>

Note: Actual review timing will be dependant upon the specific needs of the component and the program.

Participants:

Lead: PD Engineer

Support: STA Site Engineer, MP&L Representative, Buyer

On-Site Evaluation #1- APQP/PPAP Focus 第一次现场评审会议的APQP/PPAP关注点



APQP/PPAP Element Focus



5 of 31 Elements / 8 Deliverables

	APQP/PPAP Element + Deliverables	Lead
1	Sourcing decision 1. Required Sourcing Agreement Signed 2. Required Supplier Commercial & Program Agreements Signed 4. Final Mix, Maximum Weekly Volume Communicated and Agreed	Buyer
2	Customer input requirements 5. Program Expectations Cascaded to Suppliers	PD
4	DFMEA 8. DFMEA Completed 9. Special Characteristics Cascaded to Supplier	PD
8	Facilities, tools, & gauges 17. Supplier's OEE Plan is Confirmed by Surrogate Data	STA
11	Drawing & specification/design records 24. Design Styling Confirmation	PD


On-Site Evaluation #1- Expected Outputs 第一次现场评审会议的输出



	Output	Responsibility
1	Updated Supplier APQP/PPAP Readiness Assessment – Schedule A – Confirmation of 8 Required Deliverable Status更新的A表-确认11个要求的交付完成状态。	Supplier (with Cross Functional Team Consensus)
2	Agreement on Failure Mode Avoidance Strategy (Completion of DFMEA & Agreement on Special Characteristics) 完成DFMEA及特殊特性清单。	All
3	Agreement that Capacity Plan is Achievable and Consistent with CJLR Requirements 确定产能计划可行并满足CJLR要求。	STA
4	Plan developed to support prototype builds (prototype control plan & build plan) 完成样件控制计划及制造计划。	PD
5	Updated Manufacturing Site Assessment (MSA) – As required更新的MSA报告, 若需要。	STA
6	Agreement of timing for next on-site evaluations 确定下次现场评审的时间。	All

On-Site Evaluation #2 第二次现场评审会议





On-Site Evaluation #2 – Key Points 第二次现场评审会议关键点



Purpose目的:

- Facilities & Tooling Planning/Installation 设备&工装规划及安装
- PFMEA & Control Plans PFEMA&控制计划
- Gauging 检具
- Staffing & Training Planning 人员准备&培训计划
- VP Prototype Build Readiness VP样件制造准备状态
- Run-at-Rate Preparation 试生产准备

Timing: PT/UN/UP: Between <FDJ> and Prior to <VP> In Plant Date (IPD)

Participants:

Lead: PD Engineer, STA Site Engineer

Support: MP&L Representative, Buyer

On-Site Evaluation #2- APQP/PPAP Focus 第二次现场评审会议的APQP/PPAP关注点



APQP/PPAP Element Focus



8 of 31 Elements / 11 Deliverables

7 11 - 41 71 1	A Licincity Todas — O of of Licincity 11 Deliverables	
	APQP/PPAP Element + Deliverables	Lead
1	Sourcing Decision 3. All Production Tool Orders Issued to Suppliers	Buyer
7	Subcontractor APQP Status 12. Sub-supplier PPAP Timing Plan Completed	STA
8	Facilities Tools & Gauges 15. Facility and Tooling Timing Plan Completed 18. Gauge Plan (including Released Gauge Drawings) Completed	STA
9	Prototype Build Control Plan 20. Prototype Build Control Plan Completed	PD
10	Prototype Builds 21. All Prototype Tool Orders Issued to Supplier 22. Prototype Parts Ordered 23. Prototype Parts Achieve 100% of Required Print Specifications	PD
11	Drawing & Specification Design Records 25. Design Release (WERS) Completed	PD
13	Team Feasibility Commitment/Customer Engineering Approval 27. Design, Process, & Timing Feasibility Confirmation	PD/STA
15	PFMEA 29. Final PFMEA Completed with Linkages	STA/PD

35


On-Site Evaluation #2- Expected Outputs 第二次现场评审会议的输出




	Output	Responsibility
1	Updated Supplier APQP/PPAP Readiness Assessment – Schedule A - Confirmation of 11 Required Deliverable Status更新的A表-确认11个要求的交付完成状态。	Supplier (with Cross Functional Team Consensus)
2	Acceptance of parts to support VP Prototype Build (prior to shipment)在零件发运前,确定VP装车零件的可接受性。	PD/STA
3	Concurrence on manufacturing plans in support of Run-at-Rate event 确定试生产制造计划。	STA
4	Agreement on PFMEA 确定PFMEA。	STA/PD
5	Updated Manufacturing Site Assessment (MSA) – As required更新的MSA报告, 若需要。	STA
6	Agreement of timing for next on-site evaluations 确定下次现场评审的时间。	All

Decision to Proceed to Phase 0: Run-at-Rate 节拍试生产计划决定







The Path to Phase 0: Run-at-Rate 节拍试生产的流程



- Phase 0: Run at Rate timing is established and committed/reported to pre-FDJ
- From Single Point of Release to achieving a successful Phase 0 the following must be achieved 节拍 试生产必须要满足以下条件:
 - Off tool 模具件 → Development —
 - Off-Tool in Home Line 模具件在生产场地

 - Off Tool & Off Process in Home Line all tooling, equipment operating as a system **AND all parameters fully developed** 模具件在生产场地,工装设备正常系统性运行,所有参数确认并稳定 → **Development** —
 - Only Ready for Phase 0 if there is agreement that no further development is necessary for Job#1 节拍
 生产后直到量产不会再有新的开发
- PPAP simply measures how well this was done


The Path to Phase 0: Run-at-Rate 节拍试生产的流程



- The activities that precede & enable Phase 0: Run-at-Rate to take place are critical. 节拍试生产 活动至关重要
- Phase 0: Run-at-Rate marks the end of planning & development 节拍试生产标志开发阶段的结束
- Phase 0: Run-at-Rate parts are used for confirming 节拍试生产的零件用于:
 - Production Validation & Material Tests 产品性能PV试验
 - Dimensional Conformance (& Appearance) 尺寸与外观认可
 - Process Stability & Capability 过程能力研究
- The information that PPAP yields confirms that the supplier is ready to supply parts to CJLR.
- PPAP status is therefore a key measure at Launch Readiness
 - At part level, at sub-assembly level, at option level.

On-Site Evaluation #3 第三次现场评审会议





On-Site Evaluation #3 – Key Points 第三次现场评审会议关键点



Purpose目的:

- Completion of PPAP Phase 1完成阶段1PPAP
 - Dimensional Results 尺寸结果
 - Production Validation Testing 试验验证
 - Process Capability 过程能力
 - Appearance Approval 外观批准

Timing: PT: After VP build and Prior to Production Validation (PV) Build In Plant Date (IPD)

UN/UP: Between <PEC> and Prior to TT Build In Plant Date (IPD)

Participants:

Lead: STA Site Engineer

• Support: PD Engineer, MP&L Representative, Buyer

On-Site Evaluation #3 – APQP/PPAP Focus 第三次现场评审会议的APQP/PPAP关注点



APQP/PPAP Element Focus



22 of 31 Elements / 24 Deliverables

	APQP/PPAP Element + Deliverables	Lead
3	Craftsmanship/Appearance Approval Report 6. AAR Approved	PD
6	DVP&R Material/Performance Test Results 11. DV Testing Complete	PD
7	Subcontractor APQP Status 13. Sub-supplier PPAP Phase 1 (or equivalent) Completed	STA
8	Facilities, Tools, and Gauges 16. Facilities/Tools/Gauges are at the Final Production Location 19. Suppliers Demonstrated OEE (Phase 0) Supports Capacity Requirements	STA
12	Engineering Change Documents 26. All CJLR Engineering Changes Approved & Recognized by the Supplier	PD
14	Manufacturing Process Flowchart/Process Flow Diagram 28. Final Process Flowchart Supports PPAP Phase 0 Event	STA
16	Measurement System Evaluation/Measurement Systems Analysis Studies 30. Gauge R&R Results <= 10% per PPAP CJLR Customer Specifics	STA
17	Qualified Laboratory Documentation 31. Supplier Internal & External Laboratory Compliance	STA
18	Checking Aids 32. Checking Aids Compliant with Part Specifications	STA

On-Site Evaluation #3 – APQP/PPAP Focus 第三次现场评审会议的APQP/PPAP关注点



APQP/PPAP Element Focus



22 of 31 Elements / 24 Deliverables

	APQP/PPAP Element + Deliverables	Lead
19	Pre-Launch Control Plan 33. Pre-Launch Control Plan Completed with Linkages	STA
20	Operator Process Instructions 34. Operator Process Instructions Completed	STA
21	Packaging Specifications 35. Packaging Approval Process Completed	MP&L
22	Production Trial Run 36. PPAP Phase 0 (Including Sub-Suppliers) Completed	STA
23	Production Control Plan 37. Production Control Plan Completed with Linkages	STA
24	Initial Process Capability 38. Initial Process Capability Results (Ppk >= 1.67)	STA
25	Dimensional Results 39. 100% of Required Measurement Points within Tolerance	STA

On-Site Evaluation #3 – APQP/PPAP Focus 第三次现场评审会议的APQP/PPAP关注点



APQP/PPAP Element Focus



22 of 31 Elements / 24 Deliverables

	APQP/PPAP Element + Deliverables	Lead
26	Production Validation Testing 40. PV Testing Complete	PD
27	Part Submission Warrant 41. PPAP Phase 1 Complete 42. PPAP Phase 2 Complete (if Single Workstream)	STA/PD
28	Bulk Materials Requirement 45. Bulk Materials Checklist Included in PPAP Submission	STA
29	Sample Product 46. Sample Product Produced with CJLR Identification	STA
30	Master Sample 47. Master Sample Approved	STA
31	Record of Compliance 48. CJLR-Specific Requirements Documented	STA


On-Site Evaluation #3- Expected Outputs 第三次现场评审会议的输出



	Output	Responsibility
1	Updated Supplier APQP/PPAP Readiness Assessment – Schedule A – Confirmation of 24 Required Deliverable Status更新的A表-确认24个要求的交付完成状态。	Supplier (with Cross Functional Team Consensus)
2	Signed Phase 1 PPAP warrant (and Phase 2 PPAP if single production workstream) 签署阶段1PSW零件提交保证书(若仅有一条生产线,则同时签署阶段2PSW零件提交保证书)。	STA/PD
3	Updated Manufacturing Site Assessment (MSA) – As required更新的MSA报告, 若需要。	STA
4	Agreement of timing for next on-site evaluations 确定下次现场评审的时间。	All

On-Site Evaluation #4 第四次现场评审会议





On-Site Evaluation #4 – APQP/PPAP Focus 第四次现场评审会议的APQP/PPAP关注点



APQP/PPAP Element Focus



4 of 31 Elements / 5 Deliverables

	APQP/PPAP Element + Deliverables	Lead
3	Craftsmanship 7. Color Changes Completed Supporting Color Harmony	PD
5	Design/Manufacturing Reviews 10. Quality Issues Closed and Effective	STA/PD
7	Subcontractor APQP Status 14. Sub-Supplier PPAP Phase 3 (or equivalent) Completed	STA
27	Part Submission Warrant 42. PPAP Phase 2 Completed (iif multiple workstreams) 43. PPAP Phase 3 Completed 44. Supplier's Demonstrated OEE (Phase 3) Supports Capacity Requirements	STA/PD

On-Site Evaluation #4 – Expected Outputs 第四次现场评审会议的输出




	Output	Responsibility
1	Updated Supplier APQP/PPAP Readiness Assessment – Schedule – Confirm Required Deliverable Status (Final Status) 更新的A表-确认所有交付状态(最终完成状态)。	Supplier (with Cross Functional Team Consensus)
2	Signed Phase 3 PPAP warrant and Capacity Analysis Report 签署阶段3PSW零件提交保证书及产能报告。	STA
3	Updated Manufacturing Site Assessment (MSA) – As required更新的MSA报告, 若需要。	STA

APQP Assessment APQP评审表



Principles of Use 使用原则:

- Completed by all Suppliers 针对所有供应商
- Submitted to CJLR <u>monthly</u> after <PTCC> 每月提交
- Consolidated <u>automatically</u> to produce all roll-up supplier deliverables & readiness reports 生成供应商交付物状态报告



APQP Assessment: Meeting cadence APQP评审表提交



Priority Suppliers 优先级供应商:


- Update the APQP Assessment monthly or before deadline of open points in SRM 每月更新系统并开口问题截至日期前更新.
- Site STA to review the APQP Assessment with the rest of the PMST prior to this monthly submission. 项目团队定期评审

Non Priority Suppliers 非优先级供应商:

- Update the APQP Assessment monthly or before deadline of open points in SRM 每月更新系统并开口问题截至日期前更新.
- Send copy of APQP Assessment to STA and PD engineers prior to submission to the CJLR program team 更新系统前将更新内容邮件发给PMST。



Element Status Section Structure



Structure: 构成

The Element Status section of the Assessment is structured in a hierarchy that includes:
APQP的构成包含以下三个层级

- -- APQP Elements 要素
- -- Deliverables 交付物
- -- Expectations 期望

The suppliers will enter their specific status ratings in this section of the document against each program milestone or build event.

对于项目节点或者造车节点的关注项需要供应商输入状态





Element Status Section -- Definitions


ELEMENT	Deliverable Number	Expectation Number	Planned Completion Date DD-MMM-YY	Expectations / Deliverables	VPP Timing	Program Milestones Dates DD-MMM-YY Engineering Milestones Dates DD-MMM-YY Builds Dates DD-MMM-YY	PTCC	UNVO	UNV1	UNV2	M-1E
11. Drawing & Specifications	s / De	sign F	Records								
		86		All Jaguar Land Rover engineering drawing requireme available to the supplier. Supplier, working jointly with following requirements on the applicable drawings: we regulatory, sufficient control points and datum surfaces compatible with existing manufacturing processes; spe	ILR Eng d, dimer , toleran	ineering, has included the nsions, SC and CCs, Safety and nces and part specifications					
 		87		Identify any specified requirements and specifications inspection techniques and request appropriate adjustn							
ľ	24			Design Styling is completed							
	25			Plan to complete P-Authority Release by FDJ + 4 weel NOTE: Some long-lead parts may be required to be re Confirm with the JLR PD Engineer that the release pla	leased e						
12. Engineering Change Doo	cumer	1t))								
		88		Develop and implement a process to manage change or new) affected by revisions in design and process sh specifications. Reference can be obtained in the "Char provided in the Supplier Request for Engineering Appr	all contir	nue to meet all applicable ementation Plan" Checklist					
,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	26			All Jaguar Land Rover engineering changes have been an authorised engineering change document.	recorde	ed, approved and recognised on					

Element:

One of the 31 unique requirements of the APQP and PPAP process



Element Status Section – Deliverables



Deliverables are the metrics used to define the status (RED/YELLOW/GREEN/COMPLETE) of the individual 31 elements.

There is at least one Deliverable for each element, but there can be multiple deliverables for each element. As noted previously, there are a total of 49 Deliverables.

Deliverables are intended to reflect, where possible, quantifiable evidence of element success or completion. Deliverables can reflect key in-process metrics like Cpk or OEE, for example.



Element Status Section -- Deliverables

ELEMENT	Deliverable Number	Expectation Number	Planned Completion Date DD-MMM-YY	Expectations / Deliverables	VPP Timing	Program Milestones Dates DD-MMM-YY Engineering Milestones Dates DD-MMM-YY Builds Dates DD-MMM-YY	PTCC	UNVO	UNV1	UNV2	M-1DJ UPV0
11. Drawing & Specifica	tions / De	sign I	Records								
		86		All Jaguar Land Rover engineering drawing requirem available to the supplier. Supplier, working jointly with following requirements on the applicable drawings we regulatory, sufficient control points and datum surface.	JLR Eng eld, dimer s, toleran	ineering, has included the sions, SC and CCs, Safety and ces and part specifications					
				compatible with existing manufacturing processes; st	ecial mat	erial characteristics.					
		87		Identify any specified requirements and specifications inspection techniques and request appropriate adjust	that canr	not be evaluated using known m engineering.					$\overline{}$
	24			Design Styling is completed	// -						
				Plan to complete P-Authority Release by FDJ + 4 we	ks.					X	
	25			NOTE: Some long-lead parts may be required to be Confirm with the JLR PD Engineer that the release pl	eleased e an suppoi	earlier (T-Release for PT0). Its program requirements.					
12. Engineering Change	Docume	nt		1 17 1112							
		88		Develop and implement a process to manage change or new) affected by revisions in design and process s specifications. Reference can be obtained in the "Cha provided in the Supplier Request for Engineering App	nall contir	nue to meet all applicable ementation Plan" Checklist					
	26			All Jaguar Land Rover engineering changes have be an authorised engineering change document.	n recorde	ed, approved and recognised on					

<u>All</u> 49 Deliverables are required to be rated with <u>every</u> submission of the Assessment 每个交付物必须要提交评估状态

Against the program milestones, Deliverables will show two color schemes:不同项目节点交付物状态有两种不同颜色显示

- <u>Light Grey With No Box</u> Forecast Period (activity is not expected in this time period, but the supplier must enter a rating to show whether or not they forecast risk to the deliverable completion in the future. 浅灰色代表该不需要在当前节点完成,但需要显示当前的潜在风险程度,预测期
- <u>Dark Grey With Black Box</u> Deliverable Start & End Points (activity is expected to begin and end between these milestones)
 深灰色代表该交付物在当前节点需要完成,完成期



Element Status Section -- Deliverables

	Number	ımber	Planned		6	Program Milestones Dates DD-MMM-YY	PTCC 09-Sep-09				PTC 14-Sep-09		PA 16-Nov-09	
	Nu.	N C	Completion		Timing	Engineering Milestones					M-1DJ	AA1	AA2	FDJ
ELEMENT	Deliverable	Expectation Number	Date DD-MMM-YY	Expectations / Deliverables	PP Ti	Dates DD-MMM-YY								05-Feb-10
	e i	xpe			>	Builds		UNV0	UNV1	UNV2	UPV0	UPV1	UPV2	
	_	3				Dates DD-MMM-YY		10-Sep-09	11-Sep-09	12-Sep-09		15-Sep-09		
I. Drawing & Specificatio	ns / De	sign	Records				\							
	пининининининининининининининининининин	86		All Jaguar Land Rover engineering drawing requiremer available to the supplier. Supplier, working jointly with J following requirements on the applicable drawings: well regulatory, sufficient control points and datum surfaces compatible with existing manufacturing processes; specific	LR Engi d, dimen toleran	neering, has included the sions, SC and CCs, Safety and ces and part specifications								
	<u></u>	87		Identify any specified requirements and specifications to inspection techniques and request appropriate adjustments.										
	24			Design Styling is completed										
	25			Plan to complete P-Authority Release by FDJ + 4 week NOTE: Some long-lead parts may be required to be re Confirm with the JLR PD Engineer that the release plan	leased e		G	G	G	G	G	G	6	С


Example:

This deliverable is rated GREEN in the Forecast period denoting there was no expected risk to completion by FDJ. 预测期用G代表该交付物在FDJ节点前完成没有风险

The Deliverable Start & End point spans <PA> to <FDJ>. The <PA> milestone is rated GREEN, and the <FDJ> milestone is rated COMPLETE. Per APQP convention, the Deliverable end point can only be rated RED (if not finished) or COMPLETE (if finished). 完成期用C代表该交付物在FDJ节点已经完成。 如果不能完成用R表示。



Element Status Section -- Expectations



Expectations are guidelines used to assist team members in the successful completion of the elements, and where applicable, help rate completion of the related deliverables. 期望用于帮助团队评估相关的交付物完成情况

While expectations can be rated RED/YELLOW/GREEN/COMPLETE, they will <u>not</u> drive the element rating – only deliverables are rolled-up to drive element ratings. 期望可以用 R/Y/G/C表示,它不能影响31个要素的完成程度,仅交付物会影响。

The ratings for expectations are intended only for internal use and communication. 期望用于内部使用和交流。

Expectations should be thought of as Quality of Event criteria





Element Status Section -- Expectations

	umber	Number	\		5	Program Milestones Dates DD-MMM-YY	PTCC 09-Sep-09				PTC 14-Sep-09		PA 16-Nov-09	
ELEMENT	le Nu	n Nu	Planned Completion Date	Expectations / Deliverables	Timing	Engineering Milestones					M-1DJ	AA1	AA2	FDJ
CCLIVICIA	o Va	ctation	DD-MMM-YY		VPP 1	Dates DD-MMM-YY								05-Feb-
	Seliv	Expe	DJ=INIINIINI=1 T		>	Builds		UNV0	UNV1	UNV2	UPV0	UPV1	UPV2	
		"	/			Dates DD-MMM-YY		10-Sep-09	11-Sep-09	12-Sep-09		15-Sep-09		
11. Drawing & Specification	ons / De	sign F	ecords											
		86		All Jaguar Land Rover engineering drawing requirem available to the supplier. Supplier, working jointly with following requirements on the applicable drawings: wregulatory, sufficient control points and datum surface compatible with existing manufacturing processes.	JLR Eng eld, dimer s, tolerar	ineering, has included the asions, SC and CCs, Safety and aces and part specifications					Y	Y	G	С
		87		Identify any specified requirements and specifications inspection techniques and request appropriate adjust	that can	not be evaluated using known mengineering.					Υ	Y	G	С
	24			Design Styling is completed							G	G	G	С
	25			Plan to complete P-Authority Release by FDJ + 4 wer NOTE: Some long-lead parts may be required to be Confirm with the JLR PD Engineer that the release pl	eleased	earlier (T-Release for PTO). rts program requirements.	G	G	G	G	G	-	-,-	C
12. Engineering Change D	ocume	nt												
		88		Develop and implement a process to manage change of new) affected by revisions in design and process s specifications. Reference can be obtained in the "Cha provided in the Supplier Request for Engineering App	nall contii inge Impl	nue to meet all applicable ementation Plan" Checklist								

Example:

These Expectations were rated YELLOW at <PTC> and AA1 showing a potential risk. 期望用Y表示在预测期PTC有潜在风险


By <FDJ>, the Expectation end points, they were rated COMPLETE. 在完成期用C表示该期望在FDJ已经完成,风险消除

Note: Expectations are not used to drive Element status. 期望不会影响要素的状态

There is no requirement to provide a Forecast rating for an Expectation. 对于期望没有要求一定要提供预测的状态

APQP: Summary of Deliverable Rating Criteria APQP的交付物状态汇总





APQP: Summary of Deliverable Rating Criteria APQP的交付物状态汇总



Prior to Required Deliverable Completion Timing 对于在预测期的交付物:

Deliverables can be rated RED, YELLOW, GREEN, or COMPLETE 状态可以用R/Y/G/C

At Required Deliverable Completion Timing 对于在完成期的交付物:

Deliverables must be rated either COMPLETE or RED. 状态可以用C/R

A deliverable must be tracked until it is complete 交付物需要一直跟踪直到完成

After Required Deliverable Timing Completion Timing (Red items only) 对于完成期未完成的交付物(红色项):

A deliverable will continue to be rated RED until it is COMPLETE. It will no longer required to be rated at subsequent milestones after it is COMPLETE. 该交付物一直用R直到完成的节点改为C,之后的节点不需要再更新状态

Summary of Reporting Process APQP评审表总结



- APQP Assessments will be completed by every supplier and submitted to CJLR on a
 monthly basis from <PTCC> to PPAP Completion 每家供应商都需要每月更新APQP直到完成
 PPAP阶段三。
- For Priority suppliers, the cross-functional team shall achieve consensus on Deliverable ratings 对于优先级供应商,PMST需要对交付物进行评审。
- Programme Reports will be generated from the Assessments 项目团队会生成APQP评估报告
- Key Escalation Issues and Actions must be explained in the Action Plan Summary the audience includes Board Members 关键的升级问题和相应对策需要在APQP的行动计划栏里列出来,并通知PMST团队。

Summary 总结




- 1. APQP "Team Sport" APQP是团队活动
- 2. Throughout the programme development cycle, the APQP Assessment is a communication and reporting tool to provide an up-to-date status on Supplier/Part health. APQP是一个交流和汇报项目最新健康状态的工具。
- 3. A cross functional product development tool that requires equal ownership from all stakeholders. APQP是一个定义了各个部门职责的产品开发的工具

31 APOP Elements

	APQP Element	Lead
1	Sourcing Decision	PUR
2	Customer Input Requirements	PD
3	Craftsmanship / AAR	PD
4	DFMEA	PD
5	Design / Manufacturing Reviews	PD/STA
6	DVP&R / Material, Performance Test Results	PD
7	Sub-supplier PPAP/APQP Status	STA
8	Facilities, Tools & Gauges	STA
9	Prototype Build Control Plan	PD/STA
10	Prototype & VP Build(s)	PUR / PD
11	Drawing & Specifications / Design Records	PD
12	Engineering Change Document	PD
13	Team Feasibility Commitment / Customer Engineering Approval	PD/STA
14	Manufacturing Process Flowchart / Process Flow Diagram	STA
15	PFMEA	STA / PD

		APQP Element	Lead
1	16	Measurement System Evaluation / Measurement System Analysis (MSA) Plan	STA
	17	Qualified Laboratory Documentation	STA
	18	Checking Aids	STA
	19	Pre-Launch Control Plan	STA
	20	Operator Process Instructions	STA
	21	Packaging Specifications	MPL
	22	Phase 0 Run-at-Rate	STA
	23	Production Control Plan / Control Plan	STA
	24	Initial Process Capability Study	STA
	25	Dimensional Results	STA
	26	Product Validation (PV) Testing	PD
	27	PSW / PPAP	STA / PD
	28	Bulk Materials Requirements	STA
	29	Sample Product	STA
	30	Master Sample	STA
	31	Record of Compliance	STA

49 Deliverables



If APQP is strictly followed PSW comes for free! 如果APQP严格执行PSW顺理成章

Summary 总结



A Case for Change of APQP management 未来将会加强对APQP的管理

- 1. There is a need to drive key deliverable owners of the APQP 强化跟踪APQP中关键的交付物
- 2. We need "input" measures through the launch process- not just the "output" PSW metric TKO/ off tool/ PACN/ etc. 将会注重投产的过程,如数据冻结、模具件生产、工程变更,不仅仅是PSW状态
- 3. We need to encourage "teamwork" and not be afraid to raise "Red" concerns (If fact this is a positive if flagged early in the Programme) 不要担心提出红色项,鼓励团队尽早识别反馈风险
- 4. We need to avoid "late surprises" 避免突发状况
- 5. We need the develop "Priority Suppliers" based upon a risk analysis 重点关注优先级供应商
- 6. Re-establish SEP process. Ensure visits 1-4 are executed and supported fully. Cross functional engagement. 建立供应商现场评审机制,确保PMST团队支持和执行4次拜访过程
- 7. We need to adopt PSW levels, dependent on level of risk to Programme (Use resource more efficiently).为了高效利用资源,基于风险不同,将PSW分为不同等级



Q&A CJLR 版权所

- Bihong Ji 季必宏
- 18962384520
- Bihong.ji@cheryjarguarlandrover.com



THANKS